

- Webinar2
  March 1<sup>st</sup>, 2022
  10 a.m. until 11:30 a.m.
- Store4HUC Energy management Tools
- Store4HUC



## Agenda

10:00- 10:05 Welcome and Opening words
[Katja Karba, Development agency Sinergija]

10:05- 10:25 Autarky Rate Tool [Robert Pratter, 4ward Energy Research Ldt.]

10:25- 10:45 Optimal Sizing Calculator [Filip Rukavina, University of Zagreb]

10:45- 11:05 Optimal Heat Source Scheduler [Filip Rukavina, University of Zagreb]





## Agenda

11:05- 11:30 Pilot action results

[Andrea Dornhofer, Energy and Innovation Centre of Weiz]

[Martina Krizmanić Pećnik, North- West Croatia Energy Agency]

[Elisa Marino, City of Cuneo]

[Štefan Žohar, Development agency Sinergija]

**Questions and Answers** 





Implementation of a thermal storage in the historical urban city of WEIZ





### **CITY OF WEIZ**



**Inhabitants:** 

2019: 11.701

(2017: 11.508)

**Employed persons:** 

2017: 11.994

**Main Strategies:** 

City – for living!

City – full of Energy!




Source: http://www.innovationszentrum-weiz.at/360-grad-weiz



#### **PILOT WEIZBERG**





Source: <a href="http://www.innovationszentrum-weiz.at/360-grad-weiz">http://www.innovationszentrum-weiz.at/360-grad-weiz</a>





- Old church at Weizberg was built in 1065 by the lords of Radmansdorf
- In November 1758 the new building was completed
- Since 2019 the Weizberg church is a basilica
  - Basilica church is under monumental protection
  - Biomass heating plant Weizberg is working insufficient
    - Too high fuel consumption
    - Too high emissions (CO, NOx, dust and volatile unburned CnHm)
- Challenge of finding an innovative solution
  - Implement a central thermal energy storage tank in connection with decentralized hot water storage tanks
    - Decrease fuel consumption & emissions
    - Increase EE & RES






#### Biomass heating plant Weizberg

- Built in 1999
- Heat supply for 12 consumers is ensured by two biomass boilers fired with regional wood chips (1500 MWh/a)
- Largest consumers
  - Hotel, parish, primary school
  - Requirements concerning monumental protection





- Protection of the landscape presupposes that landscape is not changed or threatened by the construction of the storage tank
- The zone marked in red show minor structural measures, as well as the
  uppermost part of the water buffer tank will reach out of the ground, but not
  or only barely visible for visitors of the basilica, as it is covered by bushes
  and the parish buildings





Source: W.E.I.Z. 2019



But we have also other good news!

 The building phase started in February 2020 and was completed with the installation of the water buffer storage tank

at the end of June 2020.







Costs categories	Costs [€]
Storage	55.633 <i>,</i> 75
Heating pipes	44.687,49
Regulation	18.961,07
Electrical installation	19.251,60
<b>Emergency heating station and water treatment</b>	15.466,15
Construction costs	116.174,56
Planning and tendering	22.227,90
Total excluding VAT	292.402,53

Source: W.E.I.Z. & AEE Intec 2019



#### **MONITORING RESULTS**



KPI	Initial situation	After the pilot action			
External energy needs (kWh/year)	1930 m³	1939m³			
External energy cost (€/year)	125€/t	125€/t			
CO <sub>2</sub> emissions (t/year)	29,34t	29,01t			
Autarky rate (%)	100%	100%			
Use of energy from RES (kWh/year)	1833,500 kWh	1812,965 kWh			
Hours without service interruptions/discomforts	8692,17 h	8729,75 h			
Average power peak (kW)	479 kW	409 kW			





# As construction is finished THANK YOU

https://www.youtube.com/watch?v=L3DyPew9t2s





- D.C.6.1 and D.C.6.6: WEBINAR, 1.3.2021
- Implementing photovoltaic plants and storage systems at the Manor Bračak in Croatia
- Amartina Krizmanić Pećnik

# CROATIA - THE MANOR BRAČAK



Cultural heritage Building with new technologies:

- Built in 1889.
- In 2017. reconstructed and restored in accordance with best practices in renewing heritage on the principle of energy efficiency.
- Restored to the highest standards of energy efficiency.
- Used as central place for organizations, companies and institutions interested in renewable energy.
- It also serves as business incubator for young companies.







#### **BACKGROUND OF THE PILOT**



#### **Building insulation**

- Internal wall insulation
- Energy efficient windows and doors

#### HVAC system

- Wood pellets boiler
- Micro CHP Combined Heat and Power
- Air-water heat pump
- Heat recovery ventilation system
- Efficient lighting system





#### **ENERGY PRODUCTION**



#### Photovoltaic System



- Steel canopy covers three parking spaces
- 10,8 kWp
- Overall, 36 installed PV modules on site (300 Wp/module)
- Monocrystalline PV modules
- 36 microinverters
- Grid-connected PV (surplus goes to battery and grid)
- Roof surface ~ 60m2
- Projected production ~ 11 MWh annually






#### **ENERGY STORAGE**



#### **Battery System**

- Inside the building (under the stairs)
- GREENROCK Carbocap battery system
- 8 kWh capacity
- LTO cell (lithium titanate) a modified version of the lithium-ion cell with a longer lifespan
- 20.000 cycles (3 times longer than other battery technologies)
- Safe (non-combustible, non-flammable, nonexplosive)
- Efficiency >95%
- Depth of discharge (DoD) 90%
- A source of electricity at a time when there is no sun










# **ELECTRICITY CONSUMPTION AND PRODUCTION - SAVINGS**



- Production 11,340.00 kWh per year
- Electricity
   consumption
   energy at the
   billing metering
   point average of
   20,500.00 kWh
   per year
- 55% less







- D.C.6.1 and D.C.6.6: WEBINAR, 1.3.2021
- Italian pilot intervention on the energy efficiency of the sloping elevator in the City of Cuneo
- Store4HUC | City of Cuneo | Elisa Marino

# THE PILOT ACTION IN CUNEO







#### PILOT ACTION SPECIFICS



## Pilot action, energy efficiency oriented, consists of $\rightarrow$

- PV plant installation along the runway of the elevator
- Storage unit + inverter = storage system
- Technical room for hosting all electric equipment
- Underground cable ducts



Reduce the consumption of energy from the public grid and make the system as most independent from it as possible, optimizing the energy sources management




### PILOT ACTION TESTING RESULTS




Testing period: 20 October 2021 - 19 February 2022

54% auto-production of energy coming from the PV plant/storage

46% energy provided by the public grid








## PILOT ACTION TESTING RESULTS



# <u>Testing period</u>: 20 October 2021 - 19 February 2022 Daily consumption example



#### FORECASTS FOR THE FUTURE



At least 60% of the total energy consumption of the elevator will be provided by the PV plant during Spring and Summer months









# Thank you for your attention!



Elisa Marino, Fabio Pellegrino elisa.marino@comune.cuneo.it fabio.pellegrino@comune.cuneo.it PP07 - City of Cuneo - Store4HUC



https://www.interreg-central.eu/Content.Node/Store4HUC.html





- Second Store4HUC WEBINAR

  1st of March 2022
- Paraffin based latent storages in connection with geothermal district heating system in Lendava
- Store4HUC, Štefan Žohar (DA Sinergija)

## PILOT IN LENDAVA (SI)



Paraffin based latent heat storage system in connection with the geothermal DHS







**Aim:** to change fossil fuel with RES, reduction of consumption (4.000 kWh/a or 3%) and CO<sub>2</sub> emission (22 t/a) and the costs for heating; use of innovative solution

**Target groups:** municipality/public (transferable to private sector)

**Challenge:** low temperatures in the geothermal DHS - purchase of a suitable material (PCM material, storages)

**Transferability:** unique in Slovenia - to areas with the geothermal potencial, or combined with the biomass heating system


**Sustainability:** in accordance with the current *LEC* and *SEAP*, maintenance is ensured by the municipality - owner of the infrastructure

- **1. investment:** Pipelaying and connection of the building to the geothermal network
- 2. investment: Installation of the storage system and PCM material **Progress:** Investment is FINALISED; Monitoring process IN PROGRESS

#### Installed central control system for pilot in Lendava

CENTRAL EUROPE European Regional Development Fund

The testing and monitoring works are still running ...



# PILOT IN LENDAVA (SI)





KPI	ENERGY NEEDS	ENERGY COST's	CO <sub>2</sub>	AUTARKY RATE	RES SHARE	SUPPLY SECURITY	POWER PEAK	PROFITIBI LITY	LOCAL ECONOMY
	kWh	EUR	t CO <sub>2</sub>	%	kWh	-	kWh	-	-
Pre-investment status	84.351	8.460,45	23,53	0	0	99	22,25	n/a	n/a
Target (prediction)	80.133	5.272,93	0	0	0	100	16,5	1,49	0,48
Status quo (after pilot implementation)	69.930	2.102,42	0	0	0	100	21,6	1,99	0,48



